GENERAL NOTES

A. DESIGN BASIS

A1. Building code: 2021 International Building Code as adopted by the jurisdiction.

A2. Structural concrete: ACI 318-19, Building Code Requirements for Structural Concrete.

A3. Loads: ASCE/SEI 7-16. Live loads: offices 50 psf plus 15 psf partitions; corridors above first floor 80 psf.

A4. Gravity system: cast-in-place reinforced concrete one-way slabs on beams and girders, Levels 2 to Roof.

A5. Lateral system: special reinforced concrete shear walls (not part of this sheet set extract).

B. CONCRETE

B1. Specified compressive strength f'c at 28 days:

Element	f'c (psi)	Weight
Footings and grade beams	4,000	Normalweight
Columns and beam-column joints, all levels	5,000	Normalweight
Beams, girders and slabs, Levels 2 to Roof	4,000	Normalweight
Slab on grade	4,000	Normalweight

B2. Where column concrete differs from floor concrete, column concrete shall be placed in the joint region within the column outline only, per detail 7/S-501.

B3. Clear cover: beams and girders 1-1/2 in. to stirrups; slabs 3/4 in.; columns 1-1/2 in. to ties.

C. REINFORCEMENT

C1. Deformed bars: ASTM A615 Grade 60 (fy = fyt = 60,000 psi) unless noted.

C2. Stirrups: closed or open as detailed on S-201, with 135-degree hooks.

C3. No change to bar size, spacing or grade shall be made without written acceptance of the Structural Engineer of Record. Requests shall be made by RFI with supporting calculations.

D. SUBMITTALS AND RFIs

D1. RFI responses that change reinforcement shall state the governing check with the specified material strengths of these notes.

D2. Calculations submitted by the contractor shall use the material strengths of note B1.

TALVERD & ROWE STRUCTURAL ENGINEERS
Structural Engineer of Record

LINDEN COURT OFFICE BUILDING
Job 26-900
(fictional project for evaluation)

ISSUED FOR CONSTRUCTION

Drawn: MK Checked: AR

Date: 09/14/2026 Rev: 0

GENERAL NOTES

S-001